

Building Fire Protection System

FIRE SAFETY MANAGER BRIEFING 2017

Scope

- Buildings Requiring Fire Certificate (FC)
- Roles of Fire Safety Managers During FC Inspections
- Common Findings During FC Audit Inspections



Buildings Requiring FC


Section 20 of Fire Safety Act

- Industrial buildings
- (a) Has an occupant load of at least 1,000 persons;
- (b) Has a floor area or site area of at least 5,000 m²;
- (c) Exceeded 24 metres in habitable height; and

Public buildings

Any public building which has an occupant load of more than 200 persons







Supervise the maintenance of all fire safety works in the

premises







 Work closely with the Professional Engineers during the FC inspections to ensure that all fire protection systems are in order

- Fire Certificate Forms FC-01, FC-02 and FC-03
- Owner or MCST endorses on Form 1
- Professional Engineer (PE) endorses on Form 2 with Annexes
- All three parties i.e. Owner, PE and FSM endorse on Form 3

■ In Form FC-03, Fire Safety Manager's endorsement :

I, ______ (Name of FSM/Building Owner) hereby certify that the fire protection systems have been <u>maintained</u> and <u>tested by the Qualified</u> <u>Person</u> in accordance with the Code of Practice for Fire Precautions in Building, Fire Safety Act & Regulation and the relevant Code of Practice and are found to be in good working condition.




• What is the purpose of the 2 new Annexes attached to Form FC-02?

 What are the details in these Annexes that I need to know?









FC-02 for PE endorsement:

- Dry Rising System
- Wet Rising System
- Automatic Sprinkler System
- Automatic Fire Alarm System














- FC Form Annexes A-1 & A-2
- To provide additional test results/readings during inspections such as:
 - Wet Rising Main Flowrate and Pressure Test
 - Sprinkler System Water Proving Test
 - Dry Riser Hydrostatic Pressure Test
 - Private Hydrant Pressure and Flow Test
 - Staircase Pressurization Test






DRY RISING SYSTEM (IF APPLICABLE)

DRY RISER STACK NO. (List all stack readings)	HYDROSTATIC PRESSURE READING (INITIAL) (Pressure constant at 200 psi / 13.8 bar for 2 hrs.)	HYDROSTATIC PRESSURE READING (AFTER 2 HOURS)
DR 1-3	200	200
DR 2-3	200	200
DR 3-3	<mark>200</mark>	180

 Hydrostatic pressure reading of the dry riser shall remain constant at 200 psi (SS 575, Clause 10.4 : Tests in Dry Rising Main)






WET RISING SYSTEM (IF APPLICABLE)

WET RISER STACK NO. (List all stack readings)	STOREY TESTED	STATIC PRESSURE (BAR)	RUNNING PRESSURE (BAR)	FLOW RATE (LITRE/SEC)
1-1	Roof	6	3.5	38
1-2	Roof	6	3.5	38

- Water flow rate for non-residential building is 38 l/s for one stack and additional of 19 l/s for subsequent stack (SS575, table 3.2).
- Minimum running pressure of 3.5-5.5 bar
- Static pressure shall not exceed 7 bar








PRIVATE HYDRANT (WITH PUMP) (IF APPLICABLE)

PRIVATE HYDRANT NO. (List all hydrant readings)	STATIC PRESSURE (BAR)	RUNNING PRESSURE (BAR)	FLOW RATE (LITRE/SEC)		
FH-01	3.5	2	38		

- In general minimum water flow rate for non-residential buildings must be 38 l/s
- Minimum running pressure of 2 bar (SS575, Clause 3.1.2)







PRESSURIZED STAIRCASES (IF APPLICABLE)

STAIRCASE NO.	PRESSURE DIFFERENTIAL (MINIMUM 50 PA)	AVERAGE AIR VELOCITY (MINIMUM 1 M/S)	FORCE REQUIRED TO OPEN ANY DOOR (MAXIMUM 110 N)		
01	55	1.34	100		

- Pressure differential min. of 50 Pa
- Minimum 1 m/s average air velocity
- Force required to open the door max. 110N
 (Chapter 7 of Fire Code, Clause 7.2.2)







PRESSURIZED	STAIRCASES	(IF APPL	ICABLE)				
STAIRCASE NO	PRESSURE DIFFERENTIAL (MINIMUM 50 PA)		AVERAGE AIR VELOCITY (MINIMUM 1 M/S)			FORCE REQUIRED TO OPEN AN DOOR (MAXIMUM 110 N)	
SPRINKLER S' CONTROL VALVE NO.	OCATION OF CONTROL VALVE	AREA SERVED	NG TEST (IF Hazard Group	APPLICABLE) DESIGNED FLOW RATE (L/MIN)	DESIGNED	ACTUAL FLOW RATE (L/MIN)	ACTUAL RUNNING PRESSUR
							, ,
DEVIATION IT	TEMS (ITEMS	BASED O	N FORM FC	-02)			
*DEVIATION ITEMS (ITEMS BASED ON FORM FC-02) e.g. Faulty Basement Carpark Fan no. 1 (Justification by PE: To provide standby extraction fan during the replacement period.)					RECTIFICATION SCHEDULE 01/03/2016 – 01/04/2016		
*Fire Protection Systems shall not be compromised. Any deviation, PE shall provide justifications and be subjected to SCDF prior approval for the issuance of Fire Certificate.							
DATE & TIME OF TESTING BY PE: NAME & SIGNATURE OF PE:							

SPRINKLER PUMP WATER-PROVING TEST (IF APPLICABLE)

CONTROI VALVE NO		AREA SERVED	Hazard Group	DESIGNED FLOW RATE (L/MIN)	DESIGNED PRESSURE (KPA)	ACTUAL LOW RATE (L/MIN)	ACTUAL RUNNING PRESSURE (KPA)
CV-01	. 1st STY	1 st ,2 nd &	OH 3	1100	200	1100	860
		3rd STY		1350	170	1350	860
CV-02	4 th STY	4 th ,5 th &	OH 3	1100	<mark>270</mark>	1100	250
		6 th STY		1350	<mark>240</mark>	1350	210






Common Findings During FC Audit Inspections



Signal Transmission/DECAM System

Fire Protection System fails to send signal to the approved alarm monitoring station (Clause 6.3.7).





Fire Alarm System

 Fire alarm zone at alarm panel does not tally with the zone chart whenever there is A&A or upgrading works being carry out





Fire Door and Exit Door

- Fire door is left opened without door closer
- Dislodged door closer
- Fire door wedge opened
- Exit or Exit direction sign faulty when tested under secondary power supply







Emergency Lighting/ Pressurisation Staircase Door

Faulty emergency light along exit route



The force required to open pressurization staircase door force shall not exceed 110N







Emergency Voice Communications System





- Faulty system
- Volume too loud (echoing) or too soft (cannot hear clearly)
- Isolation of voice communications system







Portable Fire Extinguisher

- Expired date of service
- Being obstructed
- No product listing label
- Not hung in bracket









Private Hydrant





- Hydrant pit was sealed up
- Hydrant pit was filled with water and mud, unable to access valve

EM-Lock not link to alarm system



Under alarm activation mode, the electro-magnetic locks are not activated to unlock the exit door







END